

Date:-24/12/2023

To,  
The Chairman/ Secretary/ Treasurer Sir  
Raheja Residency CHS  
Sector 14, Vashi, Navi Mumbai-400 70  
Kind Atten;- \_\_\_\_\_

**Subject :- Quotation For Tremix Flooring Work At Your Society(only material and labour charges)**

Thank You Very Much For Your Flooring Enquiry We Are Pleased To Quate Our Along With Detail For The Following Work With Specification.

| Sr. No. | Description  | Unit       | Rate     |
|---------|--|------------|----------|
| 1       | Old flooring tiles and water-proofing breaking cleaning and rabbit shifting work   | Per sq.ft  | 48/-     |
| 2       | 1 <sup>st</sup> floor podium parking area base coat water proofing work and chemical coating work (Sunanda WP chemical)  | Per sq.ft  | 140/-    |
| 3       | A) M-20 Concrete supply 75 MM to 100 MM Thick concrete site mixing and shifting 1 <sup>st</sup> floor podium parking area (by lift machine)<br>B) .Tremix including necessary shuttering. application of tremix charges including fix the forms to acquire the necessary vibration by screed vibrator and leveling treatment if necessary float the surface with the power trowel and finish the same.<br>C)Non Colour Hardoner spreading work.<br>D)Stamp Crete stamping with release powder. | Per Sq.ft  | 120/-    |
| 4       | Groove cutting & groove polysulfied chemical filling Work (20 to 25 mm x 5 mm)   | Per RMT    | 150/-    |
| 5       | Recorn fiber 12mm supply per packet 900 gr   | Per packet | 450/-    |
| 6       | Transport Charges for tremix Machinery and Groove cutting Machinery.   | LS         | 10000.00 |


**Note:- The Rate Will Be Negotiable.**

If you have any questions or concerns regarding to this quotation please do not hesitate to contact us. **+9196199665479**

SEVEN HILLS BUILDCON

PROPRIETOR





**General:**

- 1) Suitable accommodation for our workmen and site incharge will be provided at your worker's colony at free of cost
- 2) Water, 3 phase electricity & light shall have to be provided free of cost at convenient point
- 3) Minimum area required per day ready for tremix flooring to be done is 250 sq mt. in case work is not done or area done is less than 250 sq mt due to non availability of site we shall be charging Rs 12000/-day
- 4) Level tolerance +/-5 mm shall have to be considered
- 5) party will responsible for our all labourers & machines & all accessories.

**Payment terms:**

- 1) The acceptance of quotation by you shall be irrevocable
- 2) 25% of the total amount of work done shall have to be paid as advance along with work order
- 3) 100% material payment shall have to be paid in advance.
- 4) Running bill be submitted at every 4000 sq.ft & payment to be made within 3 days.
- 5) Final Bill will be made as per actual measurement

**Commencement of work:-**

- On confirm order within 1-2 week from the date of acceptance of the offer

**Validity:-**

- 30 days from today

If you required any clarification please do not hesitate to contact us.

Thanking you & assuring the best service of all the time, we remain

**FOR SEVEN HILLS BUILDCON**

**PROPRIETOR**



